





Public Bid Opening Tabulation
Bid # 23-002, Murrells Inlet Bike Path Parking Facility
Wednesday, March 22, 2022 at 3:30 PM ET

Vendor Name:	TOTAL BASE BID:	Bid Bond 5%	Comments:
Associates Roofing & Construction (DBA ARC)	\$454,773.00	Yes	
Greenwave Contracting, Inc	\$548,240.00	Yes	
PSI of Conway, LLC	\$455,391.65	Yes	
RH Moore Company, Inc.	\$742,110.00	Yes	

Opened By: 

Witnessed By: 



Bid #23-002, Murrells Inlet Bike Path Parking Facility
Georgetown County Public Bid Opening Attendees

Summary

Meeting Date

Wednesday, March 22, 2023 at 3:30 PM ET

Details

Name

Nancy Silver, Georgetown County Purchasing Officer

Shanna McMahan, Georgetown County Purchasing Assistant

Andrea Ackley, Georgetown County Senior Buyer

Stacy Holland, Associates Roofing & Construction (DBA ARC)

Kent Sklpper

Ed, PSI of Conway LLC

James Chapman, Greenwave Construction

ENGINEER'S ESTIMATE

MURRELLS INLET BIKE PATH PARKING LOT
 BMI: OX1.124028; MB: 21130E
 GEORGETOWN COUNTY, SOUTH CAROLINA



DDC Engineers
 BOLTON & MENK, INC.

Date: 2/28/2023

Item No.	MnDOT Spec No.	Item	Notes	Estimated Quantity	Unit	Unit Price	Total Amount
BASE BID							
1	1031000	MOBILIZATION		1	LUMP SUM	\$10,000.00	\$10,000.00
2	1071000	TRAFFIC CONTROL		1	LUMP SUM	\$7,500.00	\$7,500.00
3	2022001	REMOVE & DISPOSE OF EXISTING CONCRETE HEADWALL		1	LUMP SUM	\$3,000.00	\$3,000.00
4	2022001	REMOVE & DISPOSE OF EXISTING LANDSCAPING		1	LUMP SUM	\$1,000.00	\$1,000.00
5	2025000	REMOVE & DISPOSE OF EXISTING ASPHALT PAVEMENT		12	SQ YD	\$50.00	\$600.00
6	2028605	CULVERT EXTENSION PREPARATION		3	EACH	\$750.00	\$2,250.00
7	2031200	SITE EXCAVATION		1	LUMP SUM	\$6,000.00	\$6,000.00
8	2036000	GEOTEXTILE FABRIC FOR SEPARATION OF SUBGRADE & BASE		340	SQ YD	\$8.00	\$2,720.00
9	2052000	NO. 57 STONE FOR BACKFILL (PERVIOUS CONCRETE)		120	TON	\$40.00	\$4,800.00
10	3050106	GRADED AGGREGATE BASE COURSE - 8" UNIFORM		820	SQ YD	\$12.00	\$9,840.00
11	3100330	HOT MIX ASPHALT BASE COURSE - TYPE C		85	TON	\$90.00	\$7,650.00
12	4030340	HOT MIX ASPHALT SURFACE COURSE - TYPE C		70	TON	\$120.00	\$8,400.00
13	5019020	PERVIOUS CONCRETE		2400	SQ FT	\$20.00	\$48,000.00
14	6052110	TRUCK MOUNTED ATTENUATOR		1	EACH	\$3,000.00	\$3,000.00
15	9510105	FLAT SHEET, TYPE III, FIXED SIZE		40	SQ FT	\$40.00	\$1,600.00
16	6271005	4" WHITE BROKEN LINE THERMOPLASTIC - 90 MIL.		160	LIN FT	\$2.00	\$320.00
17	6271010	4" WHITE SOLID LINE PAVEMENT EDGE LINE THERMOPLASTIC - 90 MIL.		700	LIN FT	\$2.00	\$1,400.00
18	7027010	DESIGN, DETAIL AND CONSTRUCT RETAINING WALL		400	SQ FT	\$35.00	\$14,000.00
19	7141112	15" RC PIPE CULVERT - CLASS III		44	LIN FT	\$60.00	\$2,640.00
20	7141113	18" RC PIPE CULVERT - CLASS III		265	LIN FT	\$80.00	\$21,200.00
21	7142532	18" RC PIPE CULVERT FLARED END SECTION - CLASS III		1	EACH	\$1,750.00	\$1,750.00
22	7192030	DROP INLET (36" X 36")		4	EACH	\$2,500.00	\$10,000.00
23	7192260	48" X 48" JUNCTION BOX		1	EACH	\$7,000.00	\$7,000.00
24	7192205	24" X 24" JUNCTION BOX		1	EACH	\$4,000.00	\$4,000.00
25	7192285	72" X 72" JUNCTION BOX		1	EACH	\$6,000.00	\$6,000.00
26	7202099	CONCRETE GUTTER-SPECIAL		760	LIN FT	\$7.50	\$5,700.00
27	7204600	CONCRETE SIDEWALK 6" UNIFORM		12	SQ YD	\$110.00	\$1,320.00
28	7204900	DETECTABLE WARNING MATERIAL		40	SQ FT	\$60.00	\$2,400.00
29	7206000	CONCRETE MEDIAN		130	SQ YD	\$110.00	\$14,300.00
30	7209000	PEDESTRIAN RAMP CONSTRUCTION		15	SQ YD	\$90.00	\$1,350.00
31	8011300	AGGREGATE UNDERDRAIN (AGGREGATE NO. 57)		420	LIN FT	\$25.00	\$10,500.00
32	8041025	RIP-RAP (CLASS B)		40	CU YD	\$120.00	\$4,800.00
33	8055300	FLEXIBLE DELINEATOR POST WITH GROUND ANCHOR		17	EACH	\$500.00	\$8,500.00
34	8100101	PERMANENT GRASSING FOR SMALL PROJECTS		0.1	ACRE	\$20,000.00	\$2,000.00
35	8152007	SEDIMENT TUBES		30	LIN FT	\$10.00	\$300.00
36	8153000	SILT FENCE		40	LIN FT	\$5.00	\$200.00
37		INLET PROTECTION		5	EACH	\$200.00	\$1,000.00
38		36" WHITE SOLID LINE CROSSWALK LINE THERMOPLASTIC - 90 MIL.		40	LIN FT	\$25.00	\$1,000.00
ESTIMATED BASE BID TOTAL:							\$238,040.00